

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements to Roads and Drains at 1st Main Nanjappa Layout in Ward No. 10 (Doddabommasandra), Vidyanarayapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N LOKANATHREDDY	
				In Figures	In Words
1	224	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	193.0	Rupees One Hundred Ninety Three Only
2	33.6	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4999.0	Rupees Four Thousand Nine Hundred Ninety Nine Only
3	70.56	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	cum	6038.0	Rupees Six Thousand Thirty Eight Only
4	4.23	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500	Tonne	57571.0	Rupees Fifty Seven Thousand Five Hundred Seventy One Only
5	537.6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	300.0	Rupees Three Hundred Only
6	201.6	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick	Sqm	645.0	Rupees Six Hundred Forty Five Only
7	1120	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded)	m	35.0	Rupees Thirty Five Only
8	201.6	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications.	Sqm	933.0	Rupees Nine Hundred Thirty Three Only
9	6.72	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications,	cum	5588.0	Rupees Five Thousand Five Hundred Eighty Eight Only

N. L. Reddy
Signature of the Contractor

N. Lokanathreddy 13/03
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Shree
13/03